



Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
		<u>BILL NO 8</u> <u>MINIATURE SUBSTATION</u> Supply miniature substations. Transport to site as per specs. Large Frame MCCB panel included for up 6 MCCBs. Danger signs and labels (Name of substation, etc. as per specifications) to be included. All civil works and earthing are included. TYPE A MINISUB: No built-in RMU TYPE B MINISUB: With built-in RMU (a) 630 kVA Type B Minature substation 8.1 .1 Supply ea 15 8.2 .2 Install ea 0 (b) 800 kVA Type B Minature substation 8.3 .1 Supply ea 2 8.4 .2 Install ea 0 (c) 1000 kVA Type B Minature substation 8.5 .1 Supply ea 3 8.6 .2 Install ea 0 (d) Provision for 1000V, 4C PVC,PVC, SWA, PVC cable works 8.7 .1 Supply lot 1 8.8 .2 Install lot 1				
		<u>BILL NO 8</u> <u>MINIATURE SUBSTATION</u>				
		Carried forward to Summary of Bills			Total	