




1 FS Elevation 1
1 : 50




3 FS Elevation 3
1 : 50



6 FS Pump House
1 : 50



2 FS Elevation 2
1 : 50




4 FS Elevation 4
1 : 50

OFF SHUTTER PAINTED
Off shutter underside of concrete slab to be skimmed and painted. Apply one coat Universal undercoat and two coats internal PVA.
Surface to be dry, sound and clean and cured for a minimum of 28 days, with a moisture content, measured with a Doser Hygrometer (or equivalent), of BD 4 scale - 5% or less.
Prime with one coat of Professional Waterbased Primer (PWP 750) with an overcoating time of 1 hour and finish with two coats of Professional Plasconsafe 200 W/B Enamel (PPS) with 4 hours drying time between coats.

WALL CONSTRUCTION
Cavity wall construction: walls to be built up using standard, galvanised butterfly wall ties at 1m centres, at 3 course intervals, staggered evenly, contractor to ensure that wind ends of ties point downwards and drip at centre of cavity. The contractor is to ensure that cavities and ties are kept clear of mortar droppings, leaving every fourth brick out above every dpc to facilitate the periodic cleaning of cavities during building operations. Every 4th perpendicular to be left unpointed / raked out to allow for drainage of cavity, weepholes @ max 1000mm intervals
Expansion joints: dow cornering 795 neutral curing silicone sealant with polycord backing cord 10mm deep to vertical and horizontal expansion joints where shown. colour: grey to match colour of pointing.

DPC
DPC to be positioned one course below threshold, under door only. DPC to be turned up 500mm on either side of door returning the dpc to its original position.

5 FS Section A-A
1 : 50



NOTE:
Do not scale from this drawing. Check all given dimensions and site dimensions and/or levels prior to any pricing, manufacturing or construction of any item. Greater detail drawings take preference. Please report any discrepancies to the Architect.

The copyright for the design and information on this drawing is vested and may not be copied or reproduced without the written authority of the Architects.

Contractor:

Tel:
Fax:
Email:

PROFESSIONAL TEAM

Project Managers : Engineering Advice & Services

73 Hough Rd, Walmer
Opebeke, 6070
Tel: 041 591 2421
Cell: 082 781 9976
Email: marcus@easpe.co.za
Web: www.easpe.co.za

Architect :

S+P Architects

123 Western Av, Vincent,
East London, 5247
Tel: +27 43 726 9327
Fax: +27 86 5406 155
Email: info@smale.co.za
Web: www.smale.co.za

Quantity Surveyors:

Pulana Baxter & Associates Quantity
Surveyors & Project Managers

30 Chamberlain Road, Berea,
East London, 5200
Postal Suite 52, P.O. Box 432, East
London, 5200
Tel: +27 43 721 0884
Email: info@pba.co.za/mark@pba.co.za
Web: www.pba.co.za

Civil Engineers :

HSC CONSULTING STRUCTURAL AND
CIVIL ENGINEERS

25 Schultz Rd, Bonnie Doon, East
London, 5200
Tel: +27 43 743 9208
Fax: +27 43 743 5347
Email: andrew@hsc.co.za
Web: www.hsc.co.za

Structural Engineers:

HSC CONSULTING STRUCTURAL AND
CIVIL ENGINEERS

25 Schultz Rd, Bonnie Doon, East
London, 5200
Tel: +27 43 743 9208
Fax: +27 43 743 5347
Email: andrew@hsc.co.za
Web: www.hsc.co.za

Electrical Engineers:

.

Tel:
Fax:
Email:

Mechanical Engineers :

.

Tel:
Fax:
Email:

Client:

EAST LONDON IDZ

P.O. Box 5458, Greenfields
East London, 5206
Lower Cheeser Road
Sunnyridge, East London, 5201
Tel: +27 43 702 8200
Fax: +27 43 738 6405
Email: info@eldz.co.za

Rev Rev Description Rev Date By To

Revision Schedule

TENDER

Email:
info@smale.co.za

Tel:
043 726 9327

Fax:
086 540 6155

Address:
123 Western Ave,
Vincent,
East London, 5247



EB/NW/10/24/Z1A

Project Name

Project Address: ELIDZ
Zone A1
NW1

Client: ELIDZ

Fire Pump House

Drawing Title

Author Drawn By Approver Approved By 05/18/25 Issued Date

Checker Checked By 7513 SACAP No. 1 : 50 Scale

0077 Project No. TEN Work Stage A205 Drawing No. Revision